

Mary Rhodes Pipeline Condition Assessment

DRAFT

Drew Molly, P.E., Chief Operations Officer

Nicholas Winkelmann, P.E., Interim Director Water Systems and Support Services

Esteban Ramos, Water Resources Manager

Jerry Snead, P.E., HDR


May 21, 2024

- **Mary Rhodes Pipeline (MRP) I**

- 101-mile-long pipeline running from Lake Texana near Edna, Texas to the O.N. Stevens Water Treatment Plant
- Construction started in 1997, completed in 1998

- **Mary Rhodes Pipeline (MRP) II**

- 42-mile-long pipeline that ties into MRP Phase I at the West Delivery Pump Station
- Construction started in 2014, completed in 2016



MRP I and II Water Sources



Lake Texana

MRP I

Contract Minimum Amount Take or Pay: 31,440 acre-ft.

Interruptible A (if available): 4,500 acre-ft.

Interruptible B (if available): 7,500 acre-ft.



Colorado River

MRP II

Run of the River Water Rights: 35,000 acre-ft.

Eastern Basin (LNRA and Colorado River) Water Availability vs. Water Taken

Source	Qty	2021	2022	2023
Contract Water Amount (MRP I - Lake Texana/LNRA)	31,440 acre-ft.	28,563 (91%)	32,147 (102%)	30,423 (97%)
Interruptible A Diversions 4,500 (I.A)	4,500 acre-ft.	4,500 (100%)	4,500 (100%)	4,500 (100%)
Interruptible B Diversions 7,500 (I.B)	7,500 acre-ft.	7,500 (100%)	Not offered	Only 4,500 offered (100%)
Water Rights Amount (MRP II - Colorado River)	35,000 acre-ft.	9,326 (27%)	10,900 (31%)	7,866 (22%)

MRP I and II Operational and Contractual Expenses

Source	FY	Operational Expense	Contractual Expense
MRP I (Lake Texana)/LNRA	2021	\$ 1,039,100	\$ 8,508,183
	2022	\$ 895,995	\$ 9,393,594
	2023	\$ 1,098,004	\$ 9,136,880

Source	FY	Amount
MRP II (Colorado River)	2021	\$ 530,415
	2022	\$ 652,299
	2023	\$ 545,338

Pipeline Components

- Pipe:
 - 99 miles of 64" diameter bar-wrapped pipe
 - Approximately 1 mile of 48" diameter bar-wrapped pipe
 - Approximately 1 mile of 72" diameter pre-stressed concrete cylinder pipe
 - 41 miles of 54" diameter bar-wrapped pipe
- Key components:
 - Colorado River Intake Pump Station
 - Colorado River Booster Pump Station
 - LNRA Intake Pump Station
 - Booster pump stations located at Bloomington and Woodsboro
 - Isolation valves, air relief valves (ARVs), blowoff valves:
 - 294 ARVs (270: 2-inch, 24: 12-inch)
 - 7 in-line valves
 - 28 blowoff valves
 - 27 water crossings (7 River/Barge, 20 Creek)
 - 300 pipeline crossings
 - 7 railroad crossings
 - 24" SDI connection
 - 36" San Patricio (Dressen) connection



Pump Stations



LNRA Intake Station



Bloomington Pump Station



Woodsboro Pump Station



Colorado River Pump Station



Pumping Schedules

Pumping Schedule	MGD
Schedule 1A	11.5 MGD to 24.4 MGD
Schedule 1B	25 MGD to 32.4 MGD
Schedule 2A	34 MGD to 40 MGD
Schedule 2B	40 MGD to 46 MGD
Schedule 3	55 MGD to 58 MGD
Schedule 4	72 MGD to 79 MGD



MRP Repair Parts Inventory



- Woodsboro Pump Station


- Repair parts are kept in the pump station and in a storage container unit
 - 2- Barrel clamps (steel)
 - 3- 5/16 Closure straps (steel)
 - 2- 1/2 Saddle (steel)
 - 2- 3/8 6' Pipe Pups cut up (steel)
 - 4- 80-pound Zinc anodes
 - 15- Diapers

- Bloomington Pump Station


- Repair parts are kept in the pump station
 - 1- Barrel clamp
 - 3- 1/2 Closure straps (steel)
 - 1- 1/2 Closure strap (steel)
 - 2- 1/2 Saddle (steel)
 - 3- 35' B303 joint (Located outside)
 - 16- Diapers
 - CCW in the process of ordering 1- 24" saddle manway and have ordered 3/8 mild steel rods

Pipe Design and Pressure Class/Rating

Pressure	Steel cylinder thickness	Spirally Wound Reinforcement
100 psi	1/10"	1/4"
125 psi	4/25"	1/4"
150 psi	3/16"	5/16"
175 psi	3/16"	3/8"



AWWA C303
(Bar wrapped pipe)



Project Goals

- Determine the current condition of the pipeline
- Understand and determine causes of past failures
- Identify and implement proactive measures to ensure the useful life of the pipeline
- Investigate the feasibility of operating at increased flows without increased risk of failure
- Develop a near and long-term plan to manage and protect the asset




Project Timeline



- June 13, 2023: CCW proactively initiates condition assessment of the MRP I with council approval
- April 29, 2024: Draft condition assessment report submitted
- May 2024: Condition assessment project complete (2 months ahead of schedule)

Assessment Methods

- Internal condition assessment
 - Acoustic leak detection
 - Electromagnetic evaluation
 - Mortar and wire analysis
 - Visual
- Drone survey (aerial & water)
- Hydraulic analysis
- Soil corrosivity analysis
- External condition assessment



Findings and Observations

- MRP is performing satisfactorily at the current pumping rate
 - The overall integrity of the pipe is good
 - Acoustic ball inspections identified three small leaks which have been repaired
- Past failures are typically associated with access points, air relief valves, joints
- Erosion areas reducing the cover over the pipeline have been identified at various water crossings




Findings and Observations

- Varying soil corrosivity conditions exist throughout the length of the pipeline and current cathodic upgrades should continue as planned
- Pump station upgrades are needed and should continue as planned
- Pipe pressure exceedance areas have been identified




Erosion and Shallow Cover Areas




- The crossings that were surveyed and findings:
 - Lavaca River – possible shallow cover on west bank
 - Garcitas Creek – possible shallow cover on east and west banks
 - Victoria Barge Canal – possible shallow cover on west bank
 - San Antonio River – possible shallow cover on east bank
 - Mission River – possible shallow cover on east bank

Pressure Exceedance: 46 MGD (Sch. 2B)




Pressure Exceedance: 46 MGD (Sch. 2B) – LNRA to Bloomington

December 2023




Pressure Exceedance: 46 MGD (Sch. 2B) – Bloomington to Woodsboro




Pressure Exceedance: 46 MGD (Sch. 2B) – Woodsboro to ONSWTP




Pressure Exceedance: 55-58 MGD (Sch. 3)




Pressure Exceedance: 55-58 MGD (Sch. 3) – LNRA to Bloomington



Pressure Exceedance: 55-58 MGD (Sch. 3) – Bloomington to Woodsboro





Pressure Exceedance: 55-58 MGD (Sch. 3) – Woodsboro to ONSWTP



Pipe Rating and Actual Pressure

46 MGD (Sch. 2B) Garcitas Creek

58 MGD (Sch. 3) San Antonio River




Action Items and Recommendations

- Continue existing CCW operation and maintenance programs (ARV replacement, mowing, etc.)
- Install pressure monitors at identified locations and review operational pressure data
- Stabilize erosion at identified locations
- Mary Rhodes Pipeline pump station system improvements – project no. E13037
- Maintenance and upgrade of cathodic protection system – project no. 23064
- Begin design and installation of parallel MRP at pressure exceedance areas - **Discussion and decision point**

Parallel Pipeline Installation


- **Location 1**

- North side of Lavaca River to south side of Garcitas Creek = 9 miles




Parallel Pipeline Installation

- **Location 2**
 - East of Placedo = 2 miles



Parallel Pipeline Installation

- **Location 3**
 - San Antonio River Crossing = 0.5 miles



Parallel Pipeline Cost and Rate Impact

- Estimated cost:
 - \$90-\$105 million for 11 miles of 64" steel pipe (open-construction) and 0.5 miles of 64" pipe (trenchless construction)
- Estimated rate impact based on current rate model:
 - Increase of \$0.19/1,000 gallons on raw water charge



Parallel Pipeline Installation Timeline

	Timeline	CCW procurement of long lead-time items
Traditional RFQ/Design/Bid/Build	42 months	36 months
Alternative delivery (Design/Build, CMAR)	36 months	NA
Design Amendment/Bid/Build	32 months	26 months



A decorative graphic consisting of four horizontal, wavy bands of varying shades of blue (light blue, medium blue, and dark blue) that curve across the top half of the slide.

Thank you!

