

TABULATION OF BIDS

CITY OF CORPUS CHRISTI, TEXAS - CONTRACTS AND PROCUREMENT DEPT.

BID DATE: Wednesday - Nov. 13, 2019

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
<b>BASE BID - PART 4: OVERLAYS</b>									
<b>PART A - GENERAL</b>									
4-A1	MOBILIZATION	LS	1	\$ 290,000.00	\$ 290,000.00	\$ 375,000.00	\$ 375,000.00	\$ 37,500.00	\$ 37,500.00
4-A2	PROJECT BONDS AND PROJECT SPECIFIC INSURANCE	LS	1	\$ 44,000.00	\$ 44,000.00	\$ 41,000.00	\$ 41,000.00	\$ 35,000.00	\$ 35,000.00
4-A3	TRAFFIC CONTROL AND SWPPP (EXCLUDING SEDIMENT CONTROL FENCING), RESIDENTIAL STREETS, SET-UP, MAINTENANCE AND REMOVAL	EA	31	\$ 3,000.00	\$ 93,000.00	\$ 1,730.00	\$ 53,630.00	\$ 5,000.00	\$ 155,000.00
4-A4	TRAFFIC CONTROL AND SWPPP(EXCLUDING SEDIMENT CONTROL FENCING), COLLECTOR STREETS, SET-UP, MAINTENANCE AND REMOVAL	EA	7	\$ 9,300.00	\$ 65,100.00	\$ 5,670.00	\$ 39,690.00	\$ 5,500.00	\$ 38,500.00
4-A5	TRAFFIC CONTROL AND SWPPP(EXCLUDING SEDIMENT CONTROL FENCING), ARTERIAL STREETS, SET-UP, MAINTENANCE AND REMOVAL	EA	7	\$ 10,900.00	\$ 76,300.00	\$ 7,460.00	\$ 52,220.00	\$ 6,000.00	\$ 42,000.00
4-A6	OZONE DAYS	DAY	4	\$ 120.00	\$ 480.00	\$ 553.00	\$ 2,212.00	\$ 50.00	\$ 200.00
4-A7	CURB PAINTING (YELLOW NO-PARKING ZONE)	LF	60	\$ 1.10	\$ 66.00	\$ 1.10	\$ 66.00	\$ 10.00	\$ 600.00
4-A8	CURB PAINTING (RED FIRE ZONE)	LF	60	\$ 1.10	\$ 66.00	\$ 1.10	\$ 66.00	\$ 15.00	\$ 900.00
4-A9	LANDSCAPE IMPROVEMENTS, INCLUDING 4" CLEAN TOP SOIL, SOD, EXCAVATION, BACKFILL, COMPACTION, WITH ESTABLISHED GROWTH.	SY	2200	\$ 32.00	\$ 70,400.00	\$ 22.00	\$ 48,400.00	\$ 15.00	\$ 33,000.00
4-A10	TYPE 1 SELF-SUPPORTED TEMPORARY SEDIMENT CONTROL FENCE, MAINTAINED AND REMOVED	LF	2100	\$ 11.25	\$ 23,625.00	\$ 7.15	\$ 15,015.00	\$ 7.50	\$ 15,750.00
4-A11	GPS (8MM HORIZONTAL AND 15 MM VERTICAL MINIMUM ACCURACY) SURVEY OF AS BUILTS - COORDINATES SHALL BE IN TX 4205 STATE PLANE, NAD 83 AND NAVD 88 DATUM PER STREET	EA	45	\$ 1,000.00	\$ 45,000.00	\$ 3,800.00	\$ 171,000.00	\$ 2,500.00	\$ 112,500.00
4-A12	RIDE QUALITY ANALYSIS TO INCLUDE STREET SURFACE EVALUATIONS WITH CALIBRATED EQUIPMENT AND APPROVED REPORTS WITH BEFORE AND AFTER SUMMARIES FOR EACH STREET	EA	45	\$ 1,000.00	\$ 45,000.00	\$ 522.00	\$ 23,490.00	\$ 1,500.00	\$ 67,500.00
<b>SUBTOTAL PART A - GENERAL</b>					<b>\$ 753,037.00</b>		<b>\$ 821,789.00</b>		<b>\$ 538,450.00</b>
<b>PART B - STREET IMPROVEMENTS</b>									

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-B1	8" THICK RESIDENTIAL SUBGRADE AND BASE REPAIR WITH LIMESTONE BASE WITH EXCAVATION/REMOVAL PLACEMENT, PRIME COAT, COMPACTION, ETC.	SY	900	\$ 48.00	\$ 43,200.00	\$ 41.00	\$ 36,900.00	\$ 55.00	\$ 49,500.00
4-B2	8" THICK RESIDENTIAL SUBGRADE AND BASE REPAIR WITH CEMENT TREATED LIMESTONE BASE WITH EXCAVATION/REMOVAL PLACEMENT, PRIME COAT, COMPACTION, ETC.	SY	900	\$ 55.00	\$ 49,500.00	\$ 48.00	\$ 43,200.00	\$ 65.00	\$ 58,500.00
4-B3	8" DEEP RESIDENTIAL SUBGRADE AND BASE REPAIR WITH TYPE B, SAC-B, PG64-22 HMAC WITH EXCAVATION/REMOVAL PLACEMENT, TACK COAT, COMPACTION, ETC.	SY	6000	\$ 61.00	\$ 366,000.00	\$ 69.00	\$ 414,000.00	\$ 90.00	\$ 540,000.00
4-B4	10" THICK COLLECTOR/ARTERIAL SUBGRADE AND BASE REPAIR WITH LIMESTONE BASE WITH EXCAVATION/REMOVAL PLACEMENT, PRIME COAT, COMPACTION, ETC.	SY	600	\$ 57.00	\$ 34,200.00	\$ 45.00	\$ 27,000.00	\$ 60.00	\$ 36,000.00
4-B5	10" THICK COLLECTOR/ARTERIAL SUBGRADE AND BASE REPAIR WITH CEMENT TREATED LIMESTONE BASE WITH EXCAVATION/REMOVAL PLACEMENT, PRIME COAT, COMPACTION, ETC.	SY	600	\$ 58.00	\$ 34,800.00	\$ 53.00	\$ 31,800.00	\$ 75.00	\$ 45,000.00
4-B6	10" DEEP COLLECTOR/ARTERIAL SUBGRADE AND BASE REPAIR WITH TYPE B, SAC-B, PG64-22 HMAC WITH EXCAVATION/REMOVAL PLACEMENT, TACK COAT, COMPACTION, ETC.	SY	1800	\$ 76.00	\$ 136,800.00	\$ 74.00	\$ 133,200.00	\$ 100.00	\$ 180,000.00
4-B7	CEMENT FOR CEMENT TREATMENT	TON	30	\$ 170.00	\$ 5,100.00	\$ 211.00	\$ 6,330.00	\$ 300.00	\$ 9,000.00
4-B8	TX5-475 TRIAXIAL GEOGRID, WITH MATERIAL AND PROPER PLACEMENT.	SY	3000	\$ 4.50	\$ 13,500.00	\$ 3.85	\$ 11,550.00	\$ 4.00	\$ 12,000.00
4-B9	HMAC SAW CUTTING (0 TO 4" DEPTH)	LF	17100	\$ 1.65	\$ 28,215.00	\$ 0.90	\$ 15,390.00	\$ 6.50	\$ 111,150.00
4-B10	PATCHING/SMALL AREA SURFACE RESTORATION - HMAC, TYPE "D" PER TON WITH SMALL EQUIPMENT PLACEMENT, REMOVAL OF EXISTING, PLACEMENT OF NEW, COMPACTION, CURING, HAULING, ETC.	TON	150	\$ 260.00	\$ 39,000.00	\$ 219.00	\$ 32,850.00	\$ 200.00	\$ 30,000.00
4-B11	APPLICATION	LF	2400	\$ 16.50	\$ 39,600.00	\$ 1.25	\$ 3,000.00	\$ 8.00	\$ 19,200.00
4-B12	HMAC - TYPE "D" LEVEL-UP COURSE (3" DEPTH MAXIMUM)	TON	684	\$ 130.00	\$ 88,920.00	\$ 139.00	\$ 95,076.00	\$ 150.00	\$ 102,600.00

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-B13	PLANING (MILLING)(0" TO 2") WITH ALL PREPARATION MILLING OPERATIONS, HAULING, ETC.	SY	180000	\$ 5.50	\$ 990,000.00	\$ 3.50	\$ 630,000.00	\$ 3.00	\$ 540,000.00
4-B14	PROOF ROLLING WITH EQUIPMENT, OPERATOR, ETC.	HOUR	132	\$ 84.00	\$ 11,088.00	\$ 101.00	\$ 13,332.00	\$ 100.00	\$ 13,200.00
4-B15	SURFACE TREATMENT - HMAC, TYPE "D", SAC-B, PG64-22 (RESIDENTIAL ROAD MIX) PER TON WITH TACK COAT, PLACEMENT, COMPACTION, CURING, HAULING, ETC.	TON	12300	\$ 116.75	\$ 1,436,025.00	\$ 130.00	\$ 1,599,000.00	\$ 170.00	\$ 2,091,000.00
4-B16	SURFACE TREATMENT - HMAC, TYPE "D", SAC-B, PG70-22 (COLLECTOR ROAD MIX) PER TON WITH TACK COAT, PLACEMENT, COMPACTION, CURING, HAULING, ETC.	TON	2400	\$ 120.00	\$ 288,000.00	\$ 120.00	\$ 288,000.00	\$ 175.00	\$ 420,000.00
4-B17	SURFACE TREATMENT - HMAC, TYPE "D", SAC-B, PG76-22 (ARTERIAL ROAD MIX) PER TON WITH TACK COAT, PLACEMENT, COMPACTION, CURING, HAULING, ETC.	TON	2400	\$ 120.00	\$ 288,000.00	\$ 120.00	\$ 288,000.00	\$ 180.00	\$ 432,000.00
4-B21	PAVEMENT MARKING, REFLECTORIZED THERMOPLASTIC, TYPE I, 90 MIL THICKNESS - WHITE 8" SOLID	LF	2580	\$ 1.65	\$ 4,257.00	\$ 1.65	\$ 4,257.00	\$ 1.00	\$ 2,580.00
4-B22	THERMOPLASTIC, TYPE I, 90 MIL THICKNESS - WHITE 4" SOLID	LF	17400	\$ 0.85	\$ 14,790.00	\$ 0.85	\$ 14,790.00	\$ 0.60	\$ 10,440.00
4-B23	PAVEMENT MARKING, REFLECTORIZED THERMOPLASTIC, TYPE I, 90 MIL THICKNESS - WHITE 4" BROKEN	LF	12600	\$ 0.85	\$ 10,710.00	\$ 0.85	\$ 10,710.00	\$ 0.60	\$ 7,560.00
4-B24	PAVEMENT MARKING, REFLECTORIZED THERMOPLASTIC, TYPE I, 90 MIL THICKNESS - YELLOW 4" SOLID	LF	18300	\$ 0.85	\$ 15,555.00	\$ 0.85	\$ 15,555.00	\$ 0.60	\$ 10,980.00
4-B25	THERMOPLASTIC, TYPE I, 90 MIL THICKNESS - YELLOW 4" BROKEN	LF	7260	\$ 0.85	\$ 6,171.00	\$ 0.85	\$ 6,171.00	\$ 0.60	\$ 4,356.00
4-B26	RAISED PAVEMENT MARKERS (REFLECTORIZED), TYPE IC, IIAA OR IIC-R, AS APPLICABLE	EA	1500	\$ 4.40	\$ 6,600.00	\$ 4.40	\$ 6,600.00	\$ 0.60	\$ 900.00
4-B27	SPEED HUMP, MARKED WITH WHITE, TYPE C HEAT APPLIED, 125 MIL, PREFORMED THERMOPLASTIC	EA	6	\$ 330.00	\$ 1,980.00	\$ 4,640.00	\$ 27,840.00	\$ 2,750.00	\$ 16,500.00
4-B28	SPEED TABLE, MARKED WITH WHITE, TYPE C HEAT APPLIED, 125 MIL, PREFORMED THERMOPLASTIC	EA	2	\$ 330.00	\$ 660.00	\$ 6,390.00	\$ 12,780.00	\$ 3,250.00	\$ 6,500.00

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-B29	PAVEMENT MARKINGS ( 24" WIDE, WHITE, TYPE C HEAT APPLIED, 125 MIL, PREFORMED THERMOPLASTIC "STOP BAR" MARKING LINES)	LF	600	\$ 13.25	\$ 7,950.00	\$ 13.00	\$ 7,800.00	\$ 12.00	\$ 7,200.00
4-B30	PAVEMENT MARKINGS (CROSSWALK MARKINGS - TOTAL LF OF 24" WIDE, WHITE, TYPE C HEAT APPLIED, 125 MIL PREFORMED THERMOPLASTIC MARKING TAPE)	LF	12300	\$ 10.00	\$ 123,000.00	\$ 2.20	\$ 27,060.00	\$ 12.00	\$ 147,600.00
4-B31	PAVEMENT MARKINGS ("ONLY" LETTERING - WHITE, TYPE C HEAT APPLIED, 125 MIL PREFORMED THERMOPLASTIC)	EA	15	\$ 330.00	\$ 4,950.00	\$ 331.00	\$ 4,965.00	\$ 350.00	\$ 5,250.00
4-B32	PAVEMENT MARKINGS (TURN ARROW MARKINGS (THROUGH, TURN AND TURN AND THROUGH) - WHITE, TYPE C HEAT APPLIED, 125 MIL PREFORMED THERMOPLASTIC)	EA	42	\$ 250.00	\$ 10,500.00	\$ 248.00	\$ 10,416.00	\$ 250.00	\$ 10,500.00
<b>SUBTOTAL PART B - STREET IMPROVEMENTS</b>							<b>\$ 3,817,572.00</b>		<b>\$ 4,919,516.00</b>
<b>PART C - CONCRETE ACTIVITIES</b>									
4-C1	REMOVAL AND REPLACEMENT OF BETWEEN 0 TO 18 LF OF CONCRETE CURB AND GUTTER AT UP TO THREE LOCATIONS ON A SINGLE STREET, INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, GEOTEXTILE, COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	EA	90	\$ 1,300.00	\$ 117,000.00	\$ 2,110.00	\$ 189,900.00	\$ 2,500.00	\$ 225,000.00
4-C2	REMOVAL AND REPLACEMENT OF BETWEEN 18 LF TO 36 LF OF CONCRETE CURB AND GUTTER AT UP TO TWO LOCATIONS ON A SINGLE STREET, INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, GEOTEXTILE COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	EA	45	\$ 2,400.00	\$ 108,000.00	\$ 3,430.00	\$ 154,350.00	\$ 3,000.00	\$ 135,000.00

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-C3	REMOVAL AND REPLACEMENT OF OVER 36 LF OF CONCRETE CURB AND GUTTER AT A SINGLE LOCATION ON A SINGLE STREET, INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, GEOTEXTILE, COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	LF	3300	\$ 66.00	\$ 217,800.00	\$ 68.00	\$ 224,400.00	\$ 50.00	\$ 165,000.00
4-C4	REMOVAL AND REPLACEMENT OF "STANDARD" 6" CONCRETE DRIVEWAYS, APPROACHES, ASSOCIATED SIDEWALK AND CURB ANG GUTTER INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	SF	17100	\$ 13.50	\$ 230,850.00	\$ 25.00	\$ 427,500.00	\$ 18.00	\$ 307,800.00
4-C5	REMOVAL AND REPLACEMENT OF "WASHED" 6" CONCRETE DRIVEWAY APPROACHES, ASSOCIATED SIDEWALK AND CURB ANG GUTTER, INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	SF	1800	\$ 17.75	\$ 31,950.00	\$ 26.00	\$ 46,800.00	\$ 25.00	\$ 45,000.00
4-C6	REMOVAL AND REPLACEMENT OF CONCRETE VALLEY GUTTER, INCLUDING, DEMO, CONCRETE SAW CUTS, DOWELING, DISPOSAL, FORMS, REBAR, CONCRETE, GEOTEXTILE, COMPACTION, CURING, HMAC SAW CUT, HMAC PATCHING, PRIME COAT, TACK COAT, FINISH, ETC.	LF	420	\$ 180.00	\$ 75,600.00	\$ 230.00	\$ 96,600.00	\$ 121.00	\$ 50,820.00
<b>SUBTOTAL PART C - CONCRETE ACTIVITIES</b>					<b>\$ 781,200.00</b>		<b>\$ 1,139,550.00</b>		<b>\$ 928,620.00</b>
<b>PART D - MINOR UTILITY IMPROVEMENTS</b>									
4-D1	WASTEWATER MANHOLE RING & COVER ADJUSTMENT, INCLUDING NEW MANHOLE RING & COVER ASSEMBLY WITH NEW HEIGHT ADJUSTMENT RINGS, STAINLESS STEEL INFLOW INHIBITOR, AND WITH CONCRETE COLLAR, WITH DEMO DISPOSAL, FORMS, REBAR, CONCRETE, CURING COMPACTION, FINISH, ETC.	EA	42	\$ 2,000.00	\$ 84,000.00	\$ 2,750.00	\$ 115,500.00	\$ 1,500.00	\$ 63,000.00

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-D2	STORMWATER MANHOLE RING & COVER ADJUSTMENT, INCLUDING NEW MANHOLE RING & COVER ASSEMBLY WITH NEW CONCRETE COLLAR, WITH DEMO, DISPOSAL, FORMS, REBAR, CONCRETE, CURING COMPACTION, FINISH,ETC.	EA	42	\$ 1,700.00	\$ 71,400.00	\$ 2,070.00	\$ 86,940.00	\$ 1,500.00	\$ 63,000.00
4-D3	ELECTRIAL/TELECOMMUNICATIONS MANHOLE RING & COVER ADJUSTMENT, INCLUDING SALVAGING AND INSTALLING EXISTING MANHOLE RING & COVER ASSEMBLY WITH NEW CONCRETE COLLAR, INCLUDING DEMO, DISPOSAL, FORMS, REBAR, CONCRETE, CURING COMPACTION, FINISH,ETC.	EA	9	\$ 2,100.00	\$ 18,900.00	\$ 2,050.00	\$ 18,450.00	\$ 1,750.00	\$ 15,750.00
4-D4	WATER VALVE COVER ADJUSTMENT WITH NEW CAST IRON VALVE BOX AND COVER, CONCRETE COLLAR, WITH DEMO, DISPOSAL, FORMS, REBAR, CONCRETE, COMPACTION, FINISH, ETC.	EA	21	\$ 660.00	\$ 13,860.00	\$ 1,130.00	\$ 23,730.00	\$ 1,250.00	\$ 26,250.00
4-D5	GAS VALVE COVER ADJUSTMENT, WITH NEW CAST IRON VALVE BOX AND COVER, DEMO, DISPOSAL, FORMS, REBAR, CONCRETE, CURING, COMPACTION, FINISH, ETC.	EA	21	\$ 1,200.00	\$ 25,200.00	\$ 1,100.00	\$ 23,100.00	\$ 1,250.00	\$ 26,250.00
4-D6	REPLACEMENT OF CONCRETE COLLARS WITH HIGH EARLY STRENGTH CONCRETE (IN ADDITION TO UNIT PRICE) WITH ACTIVITY D1, D2, D3 & D4 ABOVE	EA	90	\$ 14.50	\$ 1,305.00	\$ 11.00	\$ 990.00	\$ 50.00	\$ 4,500.00
<b>SUBTOTAL PART D - MINOR UTILITY IMPR</b>					<b>\$ 214,665.00</b>		<b>\$ 268,710.00</b>		<b>\$ 198,750.00</b>
<b>PART E - ADA IMPROVEMENTS</b>									
4-E1	REMOVAL AND REPLACEMENT OF BETWEEN 0 TO 72 SF OF ALL TYPES OF 4" THICK CONCRETE SIDEWALK INCLUDING BUT NOT LIMITED TO STANDARD SIDEWALK, APPROACHES TO RAMPS, BIKE PATHS, ETC., AT UP TO THREE LOCATIONS ON A SINGLE STREET WITH ALL DEMO, SAW CUTS, HAULING, DISPOSAL,	EA	150	\$ 1,100.00	\$ 165,000.00	\$ 1,930.00	\$ 289,500.00	\$ 2,000.00	\$ 300,000.00

STREET PREVENTATIVE MAINTENANCE PROGRAM FY 2019 PROJECT NO. 18135A - RFB #2622				BAY LTD. 1414 VALERO WAY CORPUS CHRISTI, TEXAS		HAAS-ANDERSON LTD PO BOX 7692 CORPUS CHRISTI, TEXAS		A.ORTIZ CONSTR/PAVING 102 AIRPORT RD CORPUS CHRISTI, TEXAS	
ITEM	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT	UNIT PR	AMOUNT	UNIT PR	AMOUNT
4-E2	REMOVAL AND REPLACEMENT BETWEEN 72 SF TO 144 SF OF ALL TYPES OF 4" THICK CONCRETE SIDEWALK INCLUDING BUT NOT LIMITED TO STANDARD SIDEWALK, APPROACHES TO RAMPS, BIKE PATHS, ETC., AT UP TO TWO LOCATIONS ON A SINGLE STREET WITH ALL DEMO, SAW CUTS, HAULING, DISPOSAL, DOWELING, FORMS, REINFORCING STEEL, CONCRETE, COMPACTION, CURING, FINISHING, ETC.	EA	72	\$ 2,200.00	\$ 158,400.00	\$ 3,020.00	\$ 217,440.00	\$ 2,500.00	\$ 180,000.00
4-E3	REMOVAL AND REPLACEMENT OF GREATER THAN 144 SF OF ALL TYPES OF 4" THICK CONCRETE SIDEWALK INCLUDING BUT NOT LIMITED TO STANDARD SIDEWALK, APPROACHES TO RAMPS, BIKE PATHS, ETC., AT UP TO A SINGLE LOCATION ON A SINGLE STREET WITH ALL DEMO, SAW CUTS, HAULING, DISPOSAL, DOWELING, FORMS, REINFORCING STEEL, CONCRETE, COMPACTION, CURING, FINISHING, ETC.	SF	10200	\$ 15.25	\$ 155,550.00	\$ 17.00	\$ 173,400.00	\$ 15.00	\$ 153,000.00
4-E4	ADA COMPLIANT CONCRETE CURB RAMPS AND LANDINGS, ASSOCIATED SIDEWALK, HEADER CURB AND CURB AND GUTTER	SF	25200	\$ 24.00	\$ 604,800.00	\$ 33.00	\$ 831,600.00	\$ 20.00	\$ 504,000.00
4-E5	DEMOLITION AND REMOVAL OF ADA CURB RAMPS AND LANDINGS, ASSOCIATED SIDEWALK, HEADER CURB AND CURB AND GUTTER	SF	20400	\$ 8.20	\$ 167,280.00	\$ 10.00	\$ 204,000.00	\$ 8.00	\$ 163,200.00
4-E6	NEW 4" WIDE CONCRETE HEADER CURB (0" TO 6" HIGH) FOR OFFSET ELEVATION CHANGES	LF	1050	\$ 33.00	\$ 34,650.00	\$ 22.00	\$ 23,100.00	\$ 20.00	\$ 21,000.00
<b>SUBTOTAL PART E - ADA IMPROVEMENTS</b>					<b>\$ 1,285,680.00</b>		<b>\$ 1,739,040.00</b>		<b>\$ 1,321,200.00</b>
<b>TOTAL BASE BID PART 4 - (A THRU E)</b>					<b>\$ 7,133,653.00</b>		<b>\$ 7,786,661.00</b>		<b>\$ 7,906,536.00</b>

Shaded area indicates bidder's mathematical error, extended amounts and totals are based on bidder's unit pricing