

# ZONING REPORT

Case No.: 0613-01  
 HTE No. 13-10000018

Planning Commission Hearing Date: June 19, 2013

<b>Applicant &amp; Legal Description</b>	<b>Applicant/Owner:</b> Yorktown Oso Joint Venture <b>Legal Description/Location:</b> Being a 5.74-acre tract of land out of Lots 19, 20, 29, and 30, Section 25, Flour Bluff and Encinal Farm and Garden Tracts, located east of Rancho Vista Boulevard East, between Stampede Drive and Vaquero Drive.				
<b>Zoning Request</b>	<b>From:</b> "RS-4.5" Single-Family 4.5 District <b>To:</b> "RS-4.5/PUD" Single-Family 4.5 District with a Planned Unit Development Overlay <b>Area:</b> 5.74 acres <b>Purpose of Request:</b> To develop a single-family subdivision.				
<b>Existing Zoning and Land Uses</b>		<b>Existing Zoning District</b>	<b>Existing Land Use</b>	<b>Future Land Use</b>	
	<i>Site</i>	"RS-4.5" Single-Family 4.5	Vacant	Low Density Residential	
	<i>North</i>	"RS-6" Single-Family 6	Water	Water	
	<i>South</i>	"RS-4.5" Single-Family 4.5	Low Density Residential & Vacant	Low Density Residential	
	<i>East</i>	"RS-4.5" Single-Family 4.5	Water	Water	
	<i>West</i>	"RS-4.5" Single-Family 4.5	Vacant	Low Density Residential	
<b>ADP, Map &amp; Violations</b>	<b>Area Development Plan:</b> The subject property is located within the boundaries of the Southside Area Development Plan (ADP) and is planned for low density residential uses. The proposed rezoning to the "RS-4.5/PUD" Single-Family 4.5 District with a Planned Unit Development Overlay is consistent with the adopted Future Land Use Plan. <b>Map No.:</b> 042029 & 042030 <b>Zoning Violations:</b> None				
<b>Transportation</b>	<b>Transportation and Circulation:</b> The subject property will have access to Rancho Vista Boulevard East, which is Local Residential street.				
<b>Street R.O.W.</b>	<b>Street</b>	<b>Urban Transportation Plan Type</b>	<b>Proposed Section</b>	<b>Existing Section</b>	<b>Traffic Volume</b>
	Rancho Vista Blvd. E.	Local Residential	50' ROW 28' paved	24' ROW not paved	Not Available

**Staff Summary:**

**Requested Zoning:** The applicant is requesting a rezoning from the “RS-4.5” Single-Family 4.5 District to the “RS-4.5/PUD” Single-Family 4.5 District with a Planned Unit Development Overlay to allow construction of a gated, single-family subdivision. The purpose of the Planned Unit Development Overlay (PUD) in this case is to allow deviations of the code requirements related to the street width, sidewalks, and front yard setbacks.

**Development Plan:** The proposed single-family development will consist of 27 lots. Twenty-six lots are for single-family dwellings and one 8,765-square foot lot will be dedicated as a private park maintained by the home owners association. The development will be completed in one phase. This PUD will utilize decreased front yard setbacks, sidewalk width, and street width. The development will meet all other requirements of the “RS-4.5” Single-Family 4.5 District. The single-family lots will range in size from 7,200 square feet to 10,584 square feet, and the lot width will range from 24 feet to 75 feet. Each lot will have a two-car garage and the development will provide 20 parking spaces in designated areas along the street where fire truck access will not be impeded. The development will have one point of access to Rancho Vista Boulevard East and the internal private street will have a controlled access gate.

The following table is a comparison of the proposed development standards and the development standards of the “RS-4.5” Single-Family 4.5 District and UDC. The table states all necessary deviations from the UDC.

Minimum Dimensions	“RS-4.5” District Standards for single-family detached houses	Proposed PUD	Complies?
Lot area	4,500 sq. ft.	7,200 to 10,584 sq. ft.	Yes
Lot width	45 ft.	24 to 75 ft.	<b>No</b>
Front yard	20 ft.	5 to 20 ft.	<b>No</b>
Side yard	5 ft.	5 ft.	Yes
Rear yard	5 ft.	5 ft.	Yes
Open Space	30%	30%	Yes
Height	35 ft.	35 ft.	Yes
Private Street	28 ft.	24 to 40 ft.	<b>No</b>
Sidewalk	6 ft. on one side	5 ft. on one side	<b>No</b>

**Existing Land Uses & Zoning:** North and east of the subject property is a private lake zoned “RS-6” Single-Family 6 District and “RS-4.5” Single-Family 4.5 District. West of the subject property is vacant land zoned “RS-4.5” Single-Family 4.5 District. South of the subject property are single-family dwellings zoned “RS-4.5” Single-Family 4.5 District.

**AICUZ:** The subject property is **not** located in one of the Navy’s Air Installation Compatibility Use Zones (AICUZ).

**Comprehensive Plan & Area Development Plan (ADP) Consistency:** The subject property is located within the boundaries of the Southside Area Development Plan and the proposed rezoning is consistent with the adopted Future Land Use Plan, which slates the property for a low density residential use.

**Plat Status:** The subject property is not platted. The property will be platted in accordance with the PUD plat.

**Department Comments:**

- This Planned Unit Development utilizes decreased front yard setbacks, street widths, and sidewalk widths. The development will meet all other requirements of the “RS-4.5” Single-Family 4.5 District.
- This rezoning is compatible with the present zoning and conforming uses of nearby properties and with the character of the surrounding area. This rezoning does not have a negative impact upon the surrounding neighborhood.
- This rezoning is consistent with the Future Land Use Plan’s designation of the property as a “low density residential” use.
- PUDs allow flexibility for attractive, efficient design and can encourage development on difficult sites.

**Staff Recommendation:**


Approval of the change of zoning from the “RS-4.5” Single-Family 4.5 District to the “RS-4.5/PUD” Single-Family 4.5 District with a Planned Unit Development Overlay, subject to the following conditions:

- 1.) **Development Plan:** The Owners shall develop the Property in accordance with the Master Site Plan as shown in Exhibit C. The development of the Property is to consist of 26 single-family lots and one private park lot. The development shall be constructed in one phase.
- 2.) **Residential Lot Development Standards:** The Property must be developed in accordance with the setbacks, lot sizes, and lot widths established on the Master Site Plan and associated plat as shown in Exhibits C and D, respectively. Each lot must maintain a minimum 30% open space. Development standards not shown on the Master Site Plan or associated plat or not addressed in the conditions of this ordinance must be in accordance with the “RS-4.5” Single-Family 4.5 District.
- 3.) **Parking:** The Property shall provide 20 on-street parking spaces in designated bump-out areas shown on the Master Site Plan in Exhibit C. Additionally, each lot shall have a two-car garage. Lots 47, 52, 55, and 61 may have the garages setback at a minimum five feet from the private street.

- 4.) **Private Street Access:** Each lot shall have access to a private street with a width of not less than 24 feet, as measured from back of curb to back of curb. The private street shall be striped to indicate "Fire Lane/ No Parking." The entrance to the Property may have a controlled access gate. The controlled access gate shall be located to provide a minimum of four vehicle stacking spaces.
  
- 5.) **Pedestrian Access:** A minimum five-foot wide sidewalk is required to be constructed along one side of the internal private street and shall be located in a dedicated five-foot wide pedestrian easement.
  
- 6.) **Time Limit:** Construction of the development shall commence within 24 months from the date this modified Planned Unit Development ordinance is approved by the City Council.

<b>Public Notification</b>	Number of Notices Mailed – 58 within 200' notification area; 2 outside notification area
	<u>As of June 12, 2013:</u>
	In Favor – 0 (inside notification area); 0 (outside notification area)
	In Opposition – 0 (inside notification area); 0 (outside notification area)
For 0.00% in opposition.	

- Attachments:
1. Location Map (Existing Zoning & Notice Area)
  2. Master Site Plan
  3. Plat




Date Created: 6/6/2013  
 Prepared By: jeremym  
 Department of Development Services

## CASE: 0613-01

### 2. SITE - EXISTING ZONING, NOTICE AREA & OWNERSHIP


RM-1	Multifamily 1	IL	Light Industrial
RM-2	Multifamily 2	IH	Heavy Industrial
RM-3	Multifamily 3	PUD	Planned Unit Dev. Overlay
ON	Professional Office	RS-10	Single-Family 10
RM-AT	Multifamily AT	RS-6	Single-Family 6
CN-1	Neighborhood Commercial	RS-4.5	Single-Family 4.5
CN-2	Neighborhood Commercial	RS-TF	Two-Family
CR-1	Resort Commercial	RS-15	Single-Family 15
CR-2	Resort Commercial	RE	Residential Estate
CG-1	General Commercial	RS-TH	Townhouse
CG-2	General Commercial	SP	Special Permit
CI	Intensive Commercial	RV	Recreational Vehicle Park
CBD	Downtown Commercial	RMH	Manufactured Home
CR-3	Resort Commercial		
FR	Farm Rural		
H	Historic Overlay		
BP	Business Park		




4 Owners within 200' listed on attached ownership table



X Owners in opposition





LINE	BEARING	DISTANCE
L1	S161°17'51"E	21.21
L2	S28°42'09"W	45.00
L3	S61°17'51"E	25.00
L4	N73°42'09"E	21.21
L5	S28°42'09"W	21.21
L6	S73°42'09"W	21.21
L7	S28°42'09"W	21.21
L8	S28°42'09"W	24.00
L9	S161°17'51"E	21.21
L10	S73°42'09"W	21.21
L11	N161°17'51"W	21.21
L12	N73°42'09"E	24.00
L13	N28°42'09"E	24.00
L14	S28°42'09"W	24.00
L15	S73°42'09"W	21.21
L16	S73°42'09"W	21.21

$\Delta = 335.36'$   
 $R = 403.12'$   
 $L = 12.65'$   
 $L = 25.28'$

Rancho Vista Subdivision Unit 5  
 Vol. 67, Pgs. 627-628, Map  
 Records of Nueces County, Texas

Lot 10, Block 4  
 Rancho Vista Subdivision Unit 4  
 Vol. 67, Pgs. 509-510, Map  
 Records of Nueces County, Texas

CURVE	DELTA ANGLE	RADIUS	TANGENT	ARC LENGTH
C1	26°02'32"	403.12'	83.22'	183.23'
C2	86°47'28"	15.00'	14.18'	22.72'
C3	93°12'32"	15.00'	15.86'	24.40'



REV: June 11, 2013  
 DATE: April 19, 2013  
 SCALE: 1"=50'  
 JOB NO.: 35319B2.04  
 SHEET: 1 of 1  
 DRAWN BY: XG

**UEURBAN**  
**ENGINEERING**  
 CORPUS CHRISTI, TEXAS  
 Phone: (361) 784-3700 Fax: (361) 784-3707

PUD for  
**Rancho Vista Subdivision**  
 Unit 9

5.74 acres of land out of Lots 19, 20, 29 and 30,  
 Section 25, Flour Bluff and Encinal Farm and  
 Garden Tracts, a map of which is recorded in  
 Volume A, Pages 41-43, Map Records of Nueces  
 County, Texas.

LOCATION MAP N.T.S.

EXHIBIT C - Master Site Plan

EXHIBIT D

State of Texas  
County of Nueces  
Yorktown Oso Joint Venture, hereby certifies that it is the owner of the lands embraced within the boundaries of the foregoing plat; that it has had said lands surveyed and subdivided as shown; that streets shown are dedicated to the public use forever; that easements as shown are dedicated to the public use for the installation, operation and use of public utilities; and that this map was made for the purpose of description and dedication.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

By: Yorktown Oso Joint Venture

By: Fred Braselton, Manager

State of Texas  
County of Nueces

This instrument was acknowledged before me by Fred Braselton, as Manager of Yorktown Oso Joint Venture.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Notary Public in and for the State of Texas

State of Texas  
County of Nueces

AMERICAN BANK, hereby certifies that it holds a lien on the property owned by YORKTOWN OSO JOINT VENTURE, as shown on the foregoing map and it approves of the subdivision and dedication for the purposes and considerations therein expressed.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

By: AMERICAN BANK

By: PHILLIP J. RITLEY, Senior Lending Officer

State of Texas  
County of Nueces

This instrument was acknowledged before me by PHILLIP J. RITLEY, as Senior Lending Officer of AMERICAN BANK, on behalf of said bank.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Notary Public in and for the State of Texas

State of Texas  
County of Nueces

Related investors, Ltd., hereby certifies that it holds a lien on the property owned by Yorktown Oso Joint Venture, as shown on the foregoing map and it approves of the subdivision and dedication for the purposes and considerations therein expressed.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

By: Related Investors, Ltd.

By: Chris Ann Peterson Brown, General Partner

State of Texas  
County of Nueces

This instrument was acknowledged before me by Chris Ann Peterson Brown, as General Partner of Related Investors, Ltd, on behalf of said Partnership.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_


Notary Public in and for the State of Texas

**Notes:**

- 1.) Total platted area contains 7.06 acres of land. (Includes Street Dedication)
- 2.) Set 5/8" inch iron rods with red plastic cap stamped "URBAN ENGR C.C. TX" at all lot corners, except where noted.
- 3.) The receiving water for the storm water runoff from this property is the Oso Creek. The TCEQ has not classified the aquatic life use for the Oso Creek, but it is recognized as an environmentally sensitive area. The Oso Creek flows directly into the Oso Bay. The TCEQ has classified the aquatic life use for the Oso Bay as "exceptional" and "oyster waters" and categorized the receiving water as "contact recreation" use.
- 4.) Bearings are based on the recorded plat of Rancho Vista Subdivision Unit 4, a map of which is recorded in Volume 67, Pages 54-55, Map Records of Nueces County, Texas.
- 5.) By graphic plotting only, this property is in Zone "B" on Flood Insurance Rate Map, Community Panel No. 485494 0540 C, City of Corpus Christi, Texas, which bears an effective date of March 18, 1985 and is not in a Special Flood Hazard Area.
- 6.) All lots in this subdivision are part of a Planned Unit Development (PUD), Ordinance No. \_\_\_\_\_.
- 7.) Finished floor elevations must be a minimum of 1.0' above the base flood elevation.

*Plat of*  
**Rancho Vista Subdivision**  
*Unit 9*

7.06 acres of land out of Lots 19, 20, 29 and 30, Section 25, Flour Bluff and Encinal Farm and Garden Tracts, a map of which is recorded in Volume A, Pages 41-43, Map Records of Nueces County, Texas.



LOCATION MAP N.T.S.

State of Texas  
County of Nueces

This final plat of the herein described property was approved by the Department of Development Services of the City of Corpus Christi, Texas.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Renee T. Couture, P.E.  
Development Services Engineer

State of Texas  
County of Nueces

This final plat of the herein described property was approved on behalf of the City of Corpus Christi, Texas by the Planning Commission.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Mark Van Vleet, P.E.  
Secretary

State of Texas  
County of Nueces

I, Diana T. Barrera, Clerk of the County Court in and for said County, do hereby certify that the foregoing instrument dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_ with its certificate of authentication was filed for record in my office the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, at \_\_\_\_\_ o'clock \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, duly recorded Page \_\_\_\_\_ of \_\_\_\_\_ Map Records.

Witness my hand and seal of the County Court, in and for said County, at office in Corpus Christi, Texas, the day and year last written.

No. \_\_\_\_\_  
Filed for Record \_\_\_\_\_  
at \_\_\_\_\_ o'clock \_\_\_\_\_ M.

Diana T. Barrera, County Clerk  
Nueces County, Texas

By: \_\_\_\_\_  
Deputy

State of Texas  
County of Nueces

I, Keith W. Wooley, a Registered Professional Land Surveyor for Urban Engineering, have prepared the foregoing map from a survey made on the ground under my direction and is true and correct to the best of my knowledge, information and belief; I have been engaged under contract to set all Lot and Block corners as shown herein and to complete such operations with due and reasonable diligence consistent with sound professional practices.

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Keith W. Wooley, R.P.L.S.  
Texas License No. 5463

This the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Notary Public in and for the State of Texas



DATE: April 12, 2013  
SCALE: 1"=50'  
JOB NO.: 39319/B2.04  
SHEET: 1 of 2  
DRAWN BY: XG

Rancho Vista Subdivision Unit 4  
Vol. 67, Pgs. 54-55, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 1  
Vol. 64, Pgs. 225-226, Map  
Records of Nueces County, Texas

Private Lake  
15A  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas



Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas



This portion of temporary easement, recorded in Doc. No. 122,442, is hereby closed with the recording of this plat.

LINE	BEARING	DISTANCE
L1	S81°17'51"E	45.00'
L2	S28°42'09"W	45.00'
L3	S61°17'51"E	25.00'
L4	N7°34'20"E	21.21'
L5	S61°17'51"E	40.00'
L6	N28°42'09"E	24.00'
L7	S7°34'20"W	21.21'
L8	S28°42'09"W	24.00'
L9	S16°17'51"E	21.21'
L10	N16°17'51"W	21.21'
L11	N7°34'20"E	21.21'
L12	N28°42'09"E	24.00'
L13	N28°42'09"W	24.00'
L14	S28°42'09"W	24.00'
L15	S16°17'51"E	21.21'
L16	S7°34'20"W	21.21'

Rancho Vista Boulevard East  
N31°54'41"E 122.56'

Lot 10, Block 4  
Rancho Vista Subdivision Unit 5  
Vol. 67, Pgs. 627-628, Map  
Records of Nueces County, Texas

Δ=26°29'11"  
R=378.12'  
T=86.99'  
L=174.80'

Δ=89°29'19"  
R=15.00'  
T=14.87'  
L=23.43'

Δ=28°59'59"  
R=71.00'  
T=18.36'  
L=35.94'

Rancho Vista Subdivision Unit 4  
Vol. 67, Pgs. 54-55, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 1  
Vol. 64, Pgs. 225-226, Map  
Records of Nueces County, Texas

Private Lake  
15A  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas


Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

Private Lake  
15  
Rancho Vista Subdivision Unit 4A  
Vol. 67, Pgs. 509-510, Map  
Records of Nueces County, Texas

CURVE	DELTA ANGLE	RADIUS	TANGENT	ARC LENGTH
C1	26°02'32"	403.12'	83.22'	183.23'
C2	86°47'28"	15.00'	14.18'	22.72'
C3	93°12'32"	15.00'	15.86'	24.40'
C4	10°51'10"	1058.39'	100.54'	200.48'




Graphic Scale  
1"=50'

Graphic Scale  
1"=50'

Plat of  
**Rancho Vista Subdivision**  
Unit 9

7.06 acres of land out of Lots 19, 20, 29 and 30,  
Section 25, Flour Bluff and Encinal Farm and  
Garden Tracts, a map of which is recorded in  
Volume A, Pages 41-43, Map Records of Nueces  
County, Texas.

DATE: April 12, 2013  
SCALE: 1"=50'  
JOB NO.: 39319B2.04  
SHEET: 2 of 2  
DRAWN BY: XG



UEURBAN  
ENGINEERING  
CORPUS CHRISTI, TEXAS  
Phone: (361) 783-3700 Fax: (361) 783-3007