

Yorktown Boulevard Everhart Road to Staples Street BOND 2014, Proposition 1




Council Presentation April 18, 2017



Project Location







Project Vicinity







Current and Future Projects Vicinity Map







Yorktown Boulevard Existing Conditions







Yorktown Boulevard Existing Conditions







Yorktown Boulevard Existing Conditions








Yorktown Boulevard

Pavement Section



HOT MIX ASPHALT CONCRETE (HMAC)





Project Scope



Full depth reconstruction of existing 4-lane boulevard section including:

- New pavement and lane configuration matching the Bond 2004, 2008 and 2012 projects;
- Raised medians with new curb and gutter, sidewalks, bus stops, pavement markings;
- Improved intersections at Staples, Everhart and Yorkshire;
- New signalized intersection at Everhart and Staples;
- Utility improvements including water, wastewater, storm water, and gas (by City Crews);
- Improved street lighting;
- On-street bike lanes and wider sidewalks.





- Bond language included consideration for bike lanes;
- Public meeting in 2014 stated bike lanes were included;
- Project was 90% designed with on-street bike lanes at time of Bicycle Mobility Plan adoption;
- Prior Bond projects on Yorktown included on-street bike lanes;
- Will address the bike lane "dead end" at Staples Street intersection;
- Will provide better connectivity to Flour Bluff via Yorktown in the future.





- Will enhance safety for cyclists and reduce interference with vehicular traffic;
- Will provide bicycle connectivity to residential areas and destinations such as parks, schools, trails and commercial areas including Bill Witt Park and the future Del Mar campus.
- Provides continuous bicycle accommodation on Yorktown Boulevard from Rodd Field to Weber.



Yorktown Boulevard Prior Bond Projects






Yorktown Boulevard Cross Section













- Option 1: Authorize the execution of a construction contract and construct the project as designed with on-street bike lanes (RECOMMENDED).
- Option 2: Authorize the execution of a construction contract and direct staff to revise the construction drawings and negotiate a deductive change order to remove the bike lanes.
- Option 3: Reject bids and direct staff to redesign and rebid the project.



Project Schedule



2017											2018									
F	М	A	м	J	J	A	S	0	N	D	J	F	М	Α	М	J	J	Α	s	0
Þ	Bid/ Award			Construction																

Construction Estimate: 540 days 18 months