



SEE EXHIBIT 5
FOR SUB BASIN 1
MASTER PLAN



CAYO DEL OSO

- NOTES
1. LAND USE CHARACTERISTICS WERE DETERMINED FROM THE FLOUR BLUFF AREA DEVELOPMENT PLAN, SEPTEMBER 14, 2000, FROM THE ADOPTED CORPUS CHRISTI FUTURE LAND USE MAP, MAY 24, 2005 (ORDINANCE #026278) AND THROUGH A REVIEW WITH DEVELOPMENT SERVICES STAFF ON JUNE 6, 2006.
 2. IN THE ABSENCE OF EXISTING FLOW DATA, RESIDENTIAL FLOWS WERE ASSUMED TO BE 100 GAL/CAP/DAY AS PER TCEQ 30 TAC 317.4 (a), DATED JANUARY 6, 2005.
 3. ONLY DEVELOPABLE LAND WAS CONSIDERED IN THE POPULATION PROJECTION CALCULATIONS.
 4. THE SERVICE AREAS WERE DEFINED THROUGH DISCUSSIONS WITH CITY STAFF.
 5. ALL PIPE SIZES AND SLOPES MEET TCEQ RULES AS ESTABLISHED IN 30 TAC 317, EFFECTIVE JANUARY 6, 2005.
 6. THE PEAKING FACTOR WAS CALCULATED USING THE HAROLD E. BABBITT FORMULA WHICH HAS BEEN WIDELY USED IN PREVIOUS AREA MASTER PLANS.
 7. SOME MANHOLES ARE NOT SHOWN FOR CLARITY.
 8. THE SERVICE AREA WAS ASSUMED TO BE FULLY DEVELOPED.
 9. ALL OF THE ELEVATION CONTOURS WERE DERIVED FROM THE CITY OF CORPUS CHRISTI LIDAR DATA COLLECTED IN 2003.
 10. TO THE EXTENT POSSIBLE, THE UPSTREAM END OF ALL LATERALS SHALL HAVE A MINIMUM DEPTH OF 3 FEET.
 11. SOME LOCATIONS BELOW 10 FOOT ELEVATION (100 YEAR FLOOD PLAIN) MAY REQUIRE LOW PRESSURIZED PUMPING SYSTEMS TO BE PROVIDED BY PROPERTY OWNER.



SEE EXHIBIT 8
FOR SUB BASIN 4
MASTER PLAN


- LEGEND
- PROPOSED WASTEWATER LINE
 - EXISTING WASTEWATER LINE
 - PROPOSED FORCEMAIN
 - EXISTING FORCEMAIN
 - EXISTING WASTEWATER LINES OUTSIDE OF STUDY AREA
 - AREA 1A SERVICE AREA BOUNDARY
 - LIFT STATION INTERNAL BOUNDARY
 - SUB AREA BOUNDARY
 - ADJACENT SUB-BASIN BOUNDARY
 - EXISTING INDIVIDUAL ON-SITE WW TREATMENT SYSTEM
 - WATER
- SUB AREA CALLOUT
- 67.8 ac. AVERAGE DAILY FLOW
- PROPOSED LIFT STATION
 - EXISTING LIFT STATION
 - PROPOSED MANHOLE
 - EXISTING MANHOLE

SEE EXHIBIT 6
FOR SUB BASIN 3
MASTER PLAN

FINAL

CITY OF
CORPUS CHRISTI
TEXAS
WASTEWATER
DEPARTMENT

Department of Engineering Services
AUGUST 1, 2006



WASTEWATER COLLECTION SYSTEM MASTER PLAN LAGUNA MADRE WWTP SERVICE AREA SUB BASIN AREA 1A

LAGUNA
MADRE

BROWN AND CALDWELL

LNVE ENGINEERING
engineers & consultants

CIVIL * STRUCTURAL * TRANSPORTATION * SURVEYING *
MARINE * CONSTRUCTION MANAGEMENT

801 NAVIGATION, SUITE 300 CORPUS CHRISTI, TEXAS 78408
PH. (361) 883-1984 FAX (361) 883-1986 WWW.LNVEC.COM

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY DAN S. LEVENHORN, P.E. NO. 81499 ON 08-01-06. ACTIVATION OF A SEALED DOCUMENT WITHOUT FURNISHING INFORMATION TO THE RESPONDING ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

80830
Susan Linda Kelly
08-01-06

81499
Dan S. Levenhorn

EXHIBIT 7