



~ 3,600' of Proposed 8" Sewer Main @ 0.3% Slope (RED)

Starting Depth Elevation = 6' Min.
(8" Pipe + 3.5' Cover @ Elev = ~10')

Elevation Change Over Length = ~12'

13 Proposed Manholes @
Max. 300' Separation

Cost Est: \$380,004.00

Tie-In A (GREEN)
~300' of 8" Sewer Main
1 Manholes
Cost Est: \$38,026.00

Tie-In B (BLUE)
~1000' of 8" Sewer Main
2 Manholes
Cost Est: \$56,144.00

- | | |
|--------------------|----------------------|
| ● Proposed Manhole | ● Wastewater Manhole |
| — Proposed Main | — Wastewater Main |
| — Tie-In A | ■ Substation |
| — Tie-In B | □ Parcels |
| | — Streets |

PROPOSED SEWER LINE HEINES SUBSTATION

0 300
Feet
1 inch = 300 feet

CDS
muery

ENGINEERS • SURVEYORS
3411 MAGIC DRIVE • SAN ANTONIO • TEXAS • (210)581-1111
TBPE NO. F-1733 • TBPLS NO. 100495-00