

TABULATION OF BIDS CITY OF CORPUS CHRISTI - CONTRACTS AND PROCUREMENT DEPARTMENT BID DATE: WEDNESDAY - APRIL 22,2020					
	RESIDENTIAL STREET REBUILD PROGRAM PROJECT NO 18164A RFB NO. 2998			NO BIDS RECEIVED	
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT
	BASE BID C				
	<b>PART A - GENERAL</b>				
C - A1	MOBILIZATION (MAX. 5% PART A)	LS	1		
C - A2	BONDS AND INSURANCE	LS	1		
C - A3	STORMWATER POLLUTION PREVENTION PLAN (SWPPP) (PER STREET SEGMENT EXCLUDING SILT FENCE AND INLET PROTECTION)	EA	16		
C - A4	SILT FENCE (FOR SWPPP)	LF	1,030		
C - A5	INLET PROTECTION (FOR SWPPP)	EA	95		
C - A6	OZONE ACTION DAYS	DAY	16		
C - A7	TRAFFIC CONTROL (PLAN PREPARATION)	EA	16		
C - A8	TRAFFIC CONTROL (MOBILIZATION, IMPLEMENTATION, AND ADJUSTMENTS)	MO	36		
C - A9	DOOR HANGERS, PRINTED AND DELIVERED (2 PER RESIDENCE)	EA	710		
C - A10	ALLOWANCES FOR UNANTICIPATED GENERAL ACTIVITIES	LS	1		
	<b>SUBTOTAL PART A</b>				
	<b>PART B- STREET IMPROVEMENTS</b>				
C - B1	MOBILIZATION (MAX. 5% PART B)	LS	1		
C - B2	REMOVAL AND DISPOSAL OF EXISTING TOP LAYER OF PAVEMENT ASPHALT (0-2 INCH)	SY	68,323		
C - B3	REHABILITATION - REMOVAL AND DISPOSAL OF EXISTING TOP LAYER OF PAVEMENT ASPHALT OR BASE	SY-IN	52,109		
C - B4	REHABILITATION - SURFACE PREPARATION	SY	36,026		
C - B5	1.5 INCH HMAC (TYPE D)	SY	4,222		
C - B6	2 INCH HMAC (TYPE D)	SY	55,417		
C - B7	3 INCH HMAC (TYPE D)	SY	8,685		
C - B8	PRIME COAT, MC-30 (0.15 GAL/SY)	GAL	9,360		
C - B9	CRUSHED LIMESTONE BASE (TYPE A, GRADE 1-2)	SY-IN	193,786		
C - B10	TENSAR GEOGRID (TX5)	SY	2,000		
C - B11	8 INCH LIME STABILIZED SUBGRADE	SY	38,541		
C - B12	12 INCH MOISTURE CONDITIONED COMPACTED SUBGRADE	SY	32,298		

**BID DATE: WEDNESDAY - APRIL 22,2020**

RESIDENTIAL STREET REBUILD PROGRAM PROJECT NO 18164A RFB NO. 2998				NO BIDS RECEIVED	
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT
C - B13	REHABILITATION - 8 INCH LIME TREATED BASE AND SUBGRADE	SY	23,119		
C - B14	REHABILITATION - CEMENT TREATED BASE AND SUBGRADE (MIN 4")	SY-IN	21,109		
C - B15	RECONSTRUCTION - STREET EXCAVATION (0-12 INCH)	SY	32,298		
C - B16	RECONSTRUCTION - STREET EXCAVATION (12-24 INCH)	SY	3,781		
C - B17	REHABILITATION - FULL DEPTH REPAIR	SY	434		
C - B18	PAVEMENT REPAIR	SF	1,679		
C - B19	RAISED PAVEMENT MARKERS (TYPE II-B-B) (FIRE HYDRANT MARKING)	EA	28		
C - B20	CONCRETE DRIVEWAY DEMOLITION	SF	33,640		
C - B21	6-INCH CONCRETE DRIVEWAY	SF	33,640		
C - B22	ADJUSTMENT OF EXISTING MANHOLE RING\COVER IN ROADWAY (SEWER, STORM)	EA	69		
C - B23	ADJUSTMENT OF EXISTING VALVE BOX (WATER, GAS)	EA	17		
C - B24	SPEED TABLE/SPEED HUMP	EA	4		
C - B25	REMOVE EXISTING CHAIN LINK FENCE AND REPLACE WITH NEW	LF	100		
C - B26	REMOVE EXISTING WOODEN FENCE AND REPLACE WITH NEW	LF	100		
C - B27	NEW REGULATORY SIGNAGE	EA	238		
C - B28	NEW STREET BLADE NAME SIGNS	EA	198		
C - B29	RELOCATION OF EXISTING SIGNAGE	EA	10		
C - B30	REMOVAL OF EXISTING SIGNAGE	EA	187		
C - B31	SIGN SUPPORT ASSEMBLY (WEDGE ANCHOR STEEL SYSTEM)	EA	159		
C - B32	SIGN SUPPORT ASSEMBLY (TRIANGULAR SLIPBASE SYSTEM)	EA	26		
C - B33	REMOVE AND REPLACE EXISTING MAILBOX	EA	10		
C - B34	SODDING, CLEARING AND GRADING	SY	7,482		
C - B35	WATER SERVICE LINE ADJUSTMENTS	LF	2,433		
C - B36	TYPE 'C' PREFABRICATED STOP BAR STRIPING (24-INCH)	LF	288		
C - B37	TYPE 1 REFLECTIVE PAVEMENT MARKING (YELLOW) (SOLID) (4-INCH)	LF	1,060		
C - B38	RAISED PAVEMENT MARKERS (TYPE II-A-A)	EA	14		
C - B39	ALLOWANCE FOR UNANTICIPATED STREET IMPROVEMENTS	LS	1		
	<b>SUBTOTAL PART B</b>				
	<b>PART C - ADA IMPROVEMENTS</b>				
C - C1	MOBILIZATION (MAX. 5% PART C)	LS	1		

**BID DATE: WEDNESDAY - APRIL 22,2020**

<b>RESIDENTIAL STREET REBUILD PROGRAM</b> <b>PROJECT NO 18164A</b> <b>RFB NO. 2998</b>					
				<b>NO BIDS RECEIVED</b>	
<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>UNIT</b>	<b>QTY</b>	<b>UNIT PR</b>	<b>AMOUNT</b>
C - C2	4-INCH CONCRETE SIDEWALK	SF	58,238		
C - C3	SIDEWALK DEMOLITION	SF	54,306		
C - C4	CONCRETE CURB RAMP	SF	14,460		
C - C5	CURB RAMP DEMOLITION	SF	14,460		
C - C6	TYPE 'C' PREFABRICATED CROSSWALK STRIPING (12-INCH)	LF	140		
C - C7	TYPE 'C' PREFABRICATED CROSSWALK STRIPING (24-INCH)	LF	1,008		
	<b>SUBTOTAL PART C</b>				
	<b>PART D - DRAINAGE IMPROVEMENTS</b>				
C - D1	MOBILIZATION (MAX. 5% PART D)	LS	1		
C - D2	DEMOLITION OF EXISTING INLET (0 - 5 FEET DEEP)	EA	2		
C - D3	EXISTING CURB INLET TOP ADJUSTMENT (REMOVE AND REPLACE, 5' THROAT TYP.)	EA	26		
C - D4	NEW CURB INLET (5' THROAT OPENING) (I.D. 3.5' X 5') 0 - 5 FEET DEEP	EA	9		
C - D5	NEW CURB INLET (5' THROAT OPENING) (I.D. 4.5' X 5') 5 - 10 FEET DEEP	EA	2		
C - D6	NEW CURB INLET EXTENSION (5' THROAT OPENING) (I.D. 2' X 5')	EA	2		
C - D7	NEW 4-INCH CURB AND GUTTER	LF	4,192		
C - D8	NEW 6-INCH CURB AND GUTTER	LF	19,814		
C - D9	TYPE 'B' STORM MANHOLE (I.D. 4'X4') 0 - 5 FEET DEEP	EA	1		
C - D10	TYPE 'C' STORM MANHOLE (I.D. 4'X4') 5 - 7 FEET DEEP	EA	1		
C - D11	CURB & GUTTER DEMOLITION (4-INCH, 6-INCH AND DRIVEWAY)	LF	23,996		
C - D12	VALLEY GUTTER	SF	1,665		
C - D13	VALLEY GUTTER DEMOLITION	SF	1,665		
C - D14	18-INCH ARCH REINFORCED CONCRETE PIPE (CLASS IV)	LF	30		
C - D15	18-INCH REINFORCED CONCRETE PIPE (CLASS III)	LF	410		
C - D16	24-INCH ARCH REINFORCED CONCRETE PIPE (CLASS III)	LF	330		
C - D17	CONCRETE COLLAR (18-24 INCH PIPE)	EA	2		
C - D18	CONCRETE COLLAR (36 INCH PIPE)	EA	3		
C - D19	REMOVAL OF REINFORCED CONCRETE PIPE (12 - 15 INCH)	LF	70		
C - D20	REMOVAL OF REINFORCED CONCRETE PIPE (18 - 24 INCH)	LF	30		
C - D21	REMOVAL OF REINFORCED CONCRETE PIPE (36 INCH)	LF	6		
C - D22	TRENCH SAFETY FOR STORMWATER LINES (0 - 5 FEET DEEP)	LF	110		

**BID DATE: WEDNESDAY - APRIL 22,2020**

RESIDENTIAL STREET REBUILD PROGRAM PROJECT NO 18164A RFB NO. 2998				NO BIDS RECEIVED	
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PR	AMOUNT
C - D23	TRENCH SAFETY FOR STORMWATER LINES (5 - 10 FEET DEEP)	LF	300		
C - D24	TRENCH SAFETY FOR STORMWATER INLETS/ TYPE 'B' MANHOLE (0 - 5 FEET DEEP)	EA	6		
C - D25	TRENCH SAFETY FOR STORMWATER INLETS/ TYPE 'C' MANHOLE (5 - 10 FEET DEEP)	EA	1		
C - D26	ALLOWANCE FOR UNANTICIPATED STORM WATER IMPROVEMENTS	LS	1		
	<b>SUBTOTAL PART D</b>				
	<b>Part E - WATER IMPROVEMENTS</b>				
C - E1	MOBILIZATION (MAX. 5% PART E)	LS	1		
C - E2	6-INCH OR 8-INCH A.C.P. WATERLINE TO BE REMOVED AND DISPOSED	LF	30		
C - E3	6-INCH OR 8-INCH A.C.P. TO D.I. COUPLINGS	EA	2		
C - E4	6-INCH WATERLINE ADJUSTMENT	EA	1		
C - E5	8-INCH WATERLINE ADJUSTMENT	EA	1		
C - E6	FIRE HYDRANT ASSEMBLY TYPE 1 (INCLUDES MAIN LINE FITTING)	EA	1		
C - E7	FIRE HYDRANT ASSEMBLY TYPE 2 (INCLUDES MAIN LINE FITTING)	EA	1		
C - E8	ALLOWANCE FOR UNANTICIPATED WATER IMPROVEMENTS	LS	1		
	<b>SUBTOTAL PART E</b>				
	<b>Part F - WASTEWATER IMPROVEMENTS</b>				
C - F1	MOBILIZATION (MAX. 5% PART F)	LS	1		
C - F2	ALLOWANCE FOR UNANTICIPATED WASTEWATER IMPROVEMENTS	LS	1		
	<b>SUBTOTAL PART F</b>				
	<b>Part G - GAS SYSTEM IMPROVEMENTS</b>				
C - G1	MOBILIZATION (MAX. 5% PART G)	LS	1		
C - G2	EXCAVATION, BACKFILL AND COMPACTION OF TRENCH FOR GAS LINE (ADJUSTMENT TO BE COMPLETED BY THE CITY GAS DEPARTMENT)	LF	60		
	<b>SUBTOTAL PART G</b>				
	<b>TOTAL BASE BID C (Part A thru G)</b>				